

62693

RAMP SLOPE


DESIRABLE MAXIMUM 1"PER FOOT ABSOLUTE MAXIMUM $1^{1}/_{2}$ "PER FOOT

* FLARE SLOPE

DESIRABLE MAXIMUM 3" PER FOOT MINIMUM WIDTH OF FLARE 1 FOOT

** 7" SIDE CURB





TYPICAL SECTION AT GUTTER



LEGEND

----- PREFORMED JOINT FILLER


----- DUMMY JOINT ---- SLOPE BREAKPOINT FLARED CURB

** 7" SIDE CURB ♦ DEPRESSED CURB

NOTES:

PREFORMED JOINT FILLER SHALL BE PLACED AS NOTED IN STANDARD DETAILS FOR SIDEWALK CONSTRUCTION.

THIS STANDARD SHOULD BE CONSIDERED TYPICAL FOR MOST LOCATIONS. THERE MAY BE SPECIAL INSTANCES WHERE DESIGN CHANGES WILL BE REQUIRED.




ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. 90/94 (DAN RYAN EXPRESSWAY) 63rd ST TO 59th ST (FRONTAGE ROAD & RAMPS)

CITY STANDARD DETAILS SIDEWALK CONSTRUCTION DETAILS

SCALE: NONE

DRAWN BY: PHP



TYPICAL RAMP WITH FULL WALK GREATER THAN 10 FEET WIDE

TYPICAL RAMP ADJACENT TO PARKWAY

BACK OF SIDEWALK-

- PARKWAY


6' SLAB


3/4"P.J.F. KEYSTONE

3/4"P,J.F,

PARKWAY

PARKWAY





THE SLOPE FOR SIDEWALKS AND PARKWAYS REQUIRED BY THE CITY CODE IS 1" IN 3". IF EXISTING CONDITIONS ABSOLUTELY REQUIRE, THIS SLOPE MAY BE REDUCED TO A MINIMUM OF 1" IN 4" OR INCREASED TO A MAXIMUM


3/4" P.J.F.

3/4" P.J.F.

TYPICAL RAMP WITH FULL WALK

10 FEET WIDE OR LESS

BACK OF SIDEWALK



REQUIRED BY CITY CODE RAMPS FOR THE DISABLED WILL BE CONSTRUCTED AT CORNERS AS SHOWN IN THE RAMPED SIDEWALK DETAIL.

SECTION A-A

THE 1/2" AND 3/4" DIMENSIONS NOTED ON THE DRAWING REFER TO THE THICKNESS OF THE BITUMINOUS PREFORMED JOINT FILLER REQUIRED AT THE VARIOUS LOCATIONS, BITUMINOUS PREFORMED JOINT FILLER IS NOT PAID FOR SEPARATELY, BUT INCLUDED IN THE COST OF THE SIDEWALK.

CTE ENGINEERS CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC. 303 EAST WACKER DRIVE, SUITE 600 CHICAGO ILLIWOIS 60601-5212, PHONE; (312) 938-0300

3 OF 5

DATE: October 29, 2004

CHECKED BY: RMG